



Veterans Benefit Administration Regional Office Building Fort Harrison, Montana Design/Build Project

Square Footage: 22,000 sqft
Completion Date: December 2006
Budget: \$4.5 Million
Actual Cost: \$4.8 Million
Project Delivery Mode: Design/Build
Design Started: July 27, 2005
Design Completion: September 30, 2005
Construction Started: October 3, 2005
Construction Completed: December 4, 2006
Construction Type: Steel Stud Framed
Single Level

Architect: CWG Architects
Jim Brown
Contact: VA Contract Officer
Debbie Hadley
Department of Veterans Affairs
Salt Lake City, UT 84158
801-326-1795

This Design/Build project is a one-story, slab on grade structure with exterior steel stud walls and interior structural steel support for the wood roof trusses. The roofing is comprised of both composition shingles around the perimeter of the building and a single ply roof membrane at the center of the building. The exterior facade is brick with pre-cast concrete headers and sills at the windows and doors. The building exterior blends well with the other historical buildings on the Veteran Affairs complex.

The facility obtained Leadership in Energy & Environmental Design (LEED) certified level, and is the first new Veterans Affairs office in the country to achieve this venerable designation.

